



University of Sindh

Jamshoro Sindh, Pakistan

Incharge
Project Director

No.SU/EW/PD / 246
Dated: 26-01-2026

REQUEST FOR QUOTATION


All the interested contractors/ firms/ parties are invited to participate in quotations.

S.No	Name of Work	Approved Cost	Earned Money	Period of Completion
01	Construction of One Attached Washroom for Room No.14 at Teachers Hostel, University of Sindh, Jamshoro	405,567.0	5% of Bid Amount	1 Month

Issuance date	Submission date	Opening date & time	Venue
27-01-2026 on working days.	30-01-2026 at 11:00 a.m.	30-01-2026 at 12:00 noon	Office of the Project Director, University of Sindh, Jamshoro. Tel: No.022-9213214 Email: pd@usindh.edu.pk

Terms & Condition

1. Bid shall be accompanied with 5% of Bid Price as Earnest Money in shape of Pay Order / Call Deposit in favour of Incharge Project Director, Sindh University Engineering Wing, Jamshoro.
2. Any conditional or un-complete quotation will not be considered.
3. All taxes as per Govt. policy will be deducted from contractor bills.
4. Copy of CNIC must be attached with application.
5. Registration of NTN with Active Status
6. Registration with Sindh Revenue Board (SRB) with Active Status
7. Quotation must be signed, named & stamped by the authorized person.
8. The Procuring Agency may reject all or any bids subject to the relevant provisions of SPPRA.


Incharge
Project Director
S.U. Engineering Wing

Copy to:

1. The Web Administrator, University of Sindh, Jamshoro for hoisting quotation on University of Sindh Official Website.
2. Notice Board.

General Abstract

Subject **Construction of One Attached Washroom for Room No.14 at Teachers Hostel, University of Sindh, Jamshoro**

Part-A **Cost of Schedule Items (Civil)** **Rs. _____**

Part-B **Cost of Non Schedule Items (Civil)** **Rs. _____**

Part-C **Cost of Schedule Items (Plumbing)** **Rs. _____**

Part-D **Cost of Non Schedule Items (Plumbing)** **Rs. _____**

Grand Total Rs. _____

Add: 5% SRB Tax Rs. _____

Grand Total Rs. _____

Contractor

Schedule "B"

Construction of One Attached Washroom for Room No.14 at Teachers Hostel, University of Sindh, Jamshoro

Sr,	<i>I t e m s</i>	<i>Qty</i>	<i>Rate</i>	<i>Unit</i>	<i>Amount</i>
A	Civil Work (Schedule Items)				
1	Dismantling brick work in lime or cement mortar P-19/13	120.0	59.41	Pcft	7129.00
2	Dismantling C.C. reinforced separating reinforcement from concrete cleaning and straightening the same P-20/20	10.0	229.72	Pcft	2297.00
3	Excavation in rock, dressed to designed section, grades and profiles, excavated material disposed off within 100 ft. lift upto 5ft (a) Soft rock, slate, schist or laterite work with pick and crow bar P-15/6-a	72.0	26.14	Pcft	1882.00
4	Cement concrete plain including placing compacting finishing and curing complete including screening and washing of stone aggregated shattering. 1:4:8 P-24/5-i	11.0	348.83	Pcft	3837.00
5	Pacca brick work cement and mortar foundation (1:5) P-29/4-d	50.0	366.36	Pcft	18318.00
6	Damp proof course with (cement sand and shingle concrete 1:2:4) including 2 coats of asphaltic mixture 3" thick P-28/28-c	5.0	148.71	Psft	744.00
7	Pacca brick work cement and mortar G/F (1:5) P-30/5-i-d	70.0	388.34	Pcft	27184.00
8	Cement plaster ½" thick (1:5) P-52/12-b	320.0	38.75	Psft	12400.00
9	Cement plaster 3/8" thick (1:5) P-53/12-a	260.0	37.02	Psft	9625.00
10	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividing into panels (Over Roof) P-45/16+45/17	45.0	131.37	Psft	5912.00
11	Cement concrete plain including placing compacting finishing and curing complete including screening and washing of stone aggregated shattering. 1:3:6 P-24/5-h	35.0	388.67	Pcft	13603.00
12	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. P-46/25	37.0	325.4	Pcft	12040.00

13	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing P-45/24	95.0	389.36	Psft	36989.00
14	Providing and fixing G.I frames /Choukhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet I/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage , tools and plants used in making and fixing. P-76/29	17.0	690.67	Prft	11741.00
15	Providing and fixing G.I frames /Choukhats of size 7" x 2" or 4 1/2" x 3" for windows using 20 gauge G.I sheet I/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage , tools and plants used in making and fixing P-76/28	5.0	908.25	Prft	4541.00
16	Kail wood wrought joinery in doors and windows etc. panelled or glazed or fully glazed fixed in position including chowkhat, holdfast, hinges, tower bolt rubber stop cleats/G I clamp, handles and chord with hooks etc. complete(excluding sliding bolts or lock) P-57/7-ii-a	23.0	1313.65	Psft	30214.00
17	Priming coat of chalk under distemper P-53/23	250.0	3.59	Psft	898.00
18	Distemper 3 coats P-53/24-c	250.0	17.23	Psft	4308.00
19	Painting doors / windows 3 coats P-62/4-c+ii	50.0	33.10	Psft	1655.00
					205317.00
Premium quoted by the contractor _____ % above / below					
Cost of Part "A" Schedule Items (Civil)					
B	Civil Work (Non Schedule Items)				
1	Providing & Fixing Pre-Cost Roofing including Pre-Cost Girder and leveling etc complete	50.0		Psft	
Cost of Part "A" Non Schedule Items (Civil)					
C	Plumbing Work (Schedule Items)				
1	Providing, Laying UPVC Pressure Pipes of Class 'B' (equivalent make) fixing in trench i/c cutting, fitting and jointing with 'Z' joint with one rubber ring i/c testing with water to a head 61meter or 200 ft. 6" dia	10.0	2401.99	Prft	24020.00

2	Providing, Laying UPVC Pressure Pipes of Class 'B' (equivalent make) fixing in trench i/c cutting, fitting and jointing with 'Z' joint with one rubber ring i/c testing with water to a head 61meter or 200 ft. 4" dia	20.0	1262.61	Prft	25252.00
3	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with a C.I. screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 P-189/20	3	1647.07	Each	4941.00
4	Providing and fixing 24x18" lavatory basin in white glazed carthen ware complete with & including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of ½" dia chrome plated pillar taps, 1-1/2" rubber plug & chrome plated brass chain 1-1/4" dia malleable iron or C.P. brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics) P-187/8	1	9495.14	Each	9495.00
5	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern) P-187/9	1	3276.00	Each	3276.00
6	Supplying & fixing long Bib -cock of superior quality with C.Phead 1/2" dia P-198/13-a	1	2316.60	Each	2317.00
7	Supplying & fixing C.P muslim shower with double bib cock and ring pipe etc. complete P-199/19-a	1	5475.60	Each	5476.00
8	Supplying & fixing swan type pillar cock of superior quality with Single C.P. head 1/2" dia P-199/16-a	1	1029.60	Each	1030.00
9	Supplying & fixing jet shower with rod of superior quality with C.P. head 1/2" dia P-199/15-a	1	3486.30	Each	3486.00
10	Supplying fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia P-198/12-a	6	1673.10	Each	10039.00
11	Fixing floor traps of sizes with grating including cutting and making good the requisite number of holes in walls, plinth and floors and making good in 1:2:4 C.C. P-204/9	2	1170.00	Each	2340.00

12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection P-189/23	3	637.65	Each	1913.00
13	Supplying & fixing bathroom accessories set (7 pieces) i/c towel rod ,Brush holder ,soap tray ,shelf of approved quality and design etc. complete P-199/22	1	9640.80	Each	9641.00
14	Providing chambers 15"x19" (inside imension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C. 1:4:8 in foundation, " hick cement plaster 1:3 to all inside wall urfaces and to top 1" thick C.C. 1:2:4 fl. P-200/2	2	9051.80	Each	18104.00
15	Providing and Fixing Handle Value 3/4" dia P-197/5-b	1	1848.60	Each	1849.00
					123179.00
Premium quoted by the contractor _____ % above / below					
Cost of Part "C" Schedule Items (Plumbing Work)					
D	Plumbing Work (Non Schedule Items)				
1	Providing / Fixing PPR Pipe 3/4" dia including specials & fixing cutting, fitting, compleate with cost of braking thourgh walls and roof making good etc complete	390.0		Prft	
2	Providing and fixing English Commode including the cost of white / black plastic seat (Best quality) and lid with C.P. brass hinges best quality and buffers 3 gallons white glazed earthen ware low level flushing cistem with siphon fitting 1½ " dia white porcelain enameled flush bend dia and making requisite number of holes in walls , plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Master Quality or equvelent)	1		Each	
Part-D Cost of Non Schedule Item (Plumbing Work)					
Total (Part A,B,C,D)					
5% SRB Tax					
Grand Total					

79243.00 79243.00

7924.3 7924.3

0.00

0